



Pre-Installation Checklist

This guide is intended for those who have the standard factory assembled version. If your system requires extra preparation, please refer to the installation manual for further instructions.

The following checklist assumes that the following items are completed or available:

- The heat source is installed and ready for operation.
- The radiant PEX pipes are installed in the floor and the pipe ends are trimmed at 14-16 inches above the floor, and behind where the tank will be located.
- The water connections coming from the heat source have ½ inch hose barbs on them.
- A 15 amp 120 volt AC GFCI electrical outlet is installed within 4 feet of the tank.
- The thermostats are installed and the thermostat wires are run to the tank location.
- The correct amount of distilled water and antifreeze (0.92 gallons per 100ft of ½” PEX)
- Required Tools:
 - Small flat-head screwdriver
 - Hose cutter or shear.
- The HUG Hydronic Package should include:
 - Tank assembly, with pumps, hoses, and power supply installed
 - User Manual with installation instructions
 - HUG Holey Hose Holder TM (Optional)